







DESCRIPTION	QTY	UNIT	UNIT COST			TOTAL UNIT COST	TOTAL AMOUNT (DC)	OVERHEA D/CONT	TAX	PROFIT	TOTAL
			MATERIALS	LABOR	TOOLS/ EQUIP						BID AMOUNT
Pole 2	2	pcs.									
VSU Emblem	2	lot									
VSU Label	2	lot									
Precast Conc. Cup Casting Round Cup Shape	8	pcs.									
Accessories	1	lot									
											0.00
											0.00
<b>5.0 FRONT FENCE - UPPER AND LOWER CAMPUS (Type - A &amp; Type - B)</b>											
<b>a. Masonry Wall Footing for Type-A Fence Panel</b>											
Portland Cement	714	bags									
Sand, washed	35.7	cu.m.									
Gravel, 3/4" Crushed	71.4	cu.m.									
											0.00
<b>b. Filing of CHB, RC Columns and Footings for Type - A Fence Panel</b>											
4" CHB	2100	pcs.									
Portland Cement	750	bags									
Sand, washed	73	cu.m.									
Gravel, 3/4" Crushed	145	cu.m.									
Chemical Anchor Epoxy	250	tubes									
10 mm dia x 6meter def. bars	3376	pcs.									
12 mm dia x 6meter def. bars	4642	pcs.									
Tie Wire # 16	633	kl.									
											0.00
<b>c. Filing of CHB, RC Columns and Footings for Type - B Fence Panel</b>											
4" CHB	1500	pcs.									
Portland Cement	550	bags									
Sand, washed	55	cu.m.									
Gravel, 3/4" Crushed	43	cu.m.									
10 mm dia x 6meter def. bars	3504	pcs.									
12 mm dia x 6meter def. bars	5840	pcs.									
Tie Wire # 16	219	kl.									
											0.00
<b>d. Masonry Plastering including Plain Cement Finish for Type-A Fence Panel</b>											

DESCRIPTION	QTY	UNIT	UNIT COST			TOTAL UNIT COST	TOTAL AMOUNT (DC)	OVERHEA D/CONT	TAX	PROFIT	TOTAL
			MATERIALS	LABOR	TOOLS/ EQUIP						BID AMOUNT
Portland Cement	714	bags									
Sand, washed	71.4	cu.m.									
										<b>Sub-Total:</b>	0.00
<b>e. Masonry Plastering including Plain Cement Finish for Type-B Fence Panel</b>											
Portland Cement	584	bags									
Sand, washed	43.8	cu.m.									
										<b>Sub-Total:</b>	0.00
<b>f. G.I. Fencing Works</b>											
½" x ½" x 6 meter Squarebar	2856	pcs									
1-¼" x 2" x 6 meter Anglebar	250	pcs									
1-¼" x 6 meter Flatbar	357	pcs									
2" x 2" x 6 meter Anglebar	714	pcs									
Welding rod	750	kgs.									
Pre-fab G.I. spade/arrow	14280	sets									
										<b>Sub-Total:</b>	0.00
<b>g. Painting Works (Metal Surfaces)</b>											
Guilder Epoxy Enamel	181	galls.									
East Tite with Hardener	50	galls.									
Lacquer Thinner	50	ltrs.									
Masking Tape #1-½	15	roll									
Roller Tray	60	pcs.									
Baby Roller (foam)	100	pcs.									
1" Paint Brush	100	pcs.									
Sand Paper # 120	250	pcs.									
										<b>Sub-Total:</b>	0.00
										<b>Sub-Total (5.0):</b>	0.00
<b>TOTAL BID PRICE:</b>										<b>0.00</b>	

Submitted by:

\_\_\_\_\_  
Bidder