

	25 mm. dia. Schedule 40,female adaptor with locknut (PVC)	6	pcs																
	20 mm. dia. Schedule 40,female adaptor with locknut (PVC)	36	pcs																
	pvc solvent	3	pcs																
	Pull Box, Tie Wire, Support and Hangers, PVC Cup	1	lot																
	II. Wires and Wiring Devices																		
	14 mm2 THHN/THW stranded wire	100	meters																
	5.5 mm2 THHN/THW stranded wire	60	meters																
	3.5 mm2 THHN/THW stranded wire	3	boxes																
	3.5 mm2 TW (G) stranded wire	1	box																
	Duplex tamper resistant receptacle outlet with ground prong	8	pcs.																
	GFCI receptacle outlet	1	pcs.																
	aircon outlet	2	pcs.																
	1 Gang switch	3	pcs.																
	2 Gang switch	1	pcs.																
	3 Gang switch	1	pcs.																
	three way switch (one gang)	1	pcs.																
	utility box	20	pcs																
	octagonal box with cover	16	pcs																
	single phase kilowatt-hour meter with nema 3R enclosure	1	set																
	grounding rod with connector	1	set																
	electrical tape	7	pcs																
	III. Power Load Center, Switchgear and Panelboards																		
	Panel "LP" : Bolt on type with grounding termination, 8 holes	1	set																
	MAIN : 50AT/50AF,2P,10KAIC, at 240V MCCB																		
	Branches :																		
	2- 15AT,8KAIC,2P,MCCB																		
	2- 20AT,8KAIC,2P,MCCB																		
	3- 30AT,8KAIC,2P,MCCB																		
	IV. Lighting fixtures																		
	3 watts led bulb in square pinlight	6	set																
	7 watts led bulb in circular pinlight	3	set																
	9 watts led bulb in outdoor ceiling lighting fixture(cylindrical)	4	set																
	2x40 watts led tube in louver type surface mount lighting fixture 12"x48"	4	set																
	SUB-TOTAL																		
	GRAND TOTAL AMOUNT																		

Submitted by:

Bidder

