

DESCRIPTION	QTY	UNIT	UNIT COST			TOTAL UNIT COST	TOTAL	OVERHEAD/C	TAX	PROFIT	TOTAL
			MATERIALS	LABOR	TOOLS/EQUIP	DIRECT	AMOUNT (DC)	MISCEL			BID AMOUNT
Quick Dry Enamel	40	gals									
Sand Paper	400	pcs									
Paint Brush	50	pcs									
Roller Brush	100	pcs									
										Sub-Total (9.0):	-
10.0 Doors and Windows											
MD-01 Steel Door (1200 x 2100)	1	set									
MD-02 Steel Door (800 x 2100)	1	set									
WD-01 Wood Door (900 x 2100) with door jamb and hardware accessories	20	sets									
WD-02 Wood Door (800 x 2100) with door jamb and hardware accessories	13	sets									
WD-03 Wood Door with louver (700 x 2100) with door jamb and hardware accessories	10	sets									
GD-01 Glass Door (4200 x 2100) with Powder Coated aluminum Frame	4	sets									
W-01 Steel Window in Powder Coated Framing (1800 x 4800)	6	sets									
W-02 Fixed Glass Window (4200 x 475) in Powder Coated Framing	4	sets									
W-03 Jalousie Window (3980 x 1260) in Powder Coated Framing	21	set									
W-04 Jalousie Window (2390 x 1260) in Powder Coated Framing	2	sets									
W-05 Sliding Window (2400 x 1200) in Powder Coated Framing	8	sets									
W-06 Awning Window (3000 x 400) in Powder Coated Framing	3	sets									
W-07 Awning Window (2000 x 400) in Powder Coated Framing	8	sets									
W-08 Awning Window (1800 x 400) in Powder Coated Framing	10	sets									
W-09 Awning Window (1200 x 400) in Powder Coated Framing	13	sets									
Metal Works											
Installation of Steel Railings including stairs	63.98	l.m									
Installation of Decorative Steel Grills (facade)	8	lot									
Installation of patterned Lattice	1	lot									
										Sub-Total (10.0):	-

DESCRIPTION	QTY	UNIT	UNIT COST			TOTAL UNIT	TOTAL	OVERHEAD/C	TAX	PROFIT	TOTAL
			MATERIALS	LABOR	TOOLS/EQUIP	DIRECT	AMOUNT (DC)	MISCEL			BID AMOUNT
Flourescent lighting fixture box type, 2x44w	37	pcs									
Flourescent lighting fixture box type, 2x25w	196	pcs									
6" dia. Pinlight,1-12w warm white led light,in aluminum white powder coated frame	97	pcs									
6" dia. Canster light,1-12w warm white led light,in aluminum white powder coated frame	25	pc									
MAIN : 500AT/500AF,3P,25KAIC at 240V MCCB enclosed in nema 3R enclosure with grounding termination	1	set									
Panel MDP : 600A PANEL with 4 holes (with grounding termination)	1	set									
MAIN : 500AT/500AF,3P,25KAIC at 240V MCCB	1										
Branches :											
150AT,18KAIC,3P,MCCB	1										
200AT,18KAIC,3P,MCCB	2										
Panel LP : 250A PANEL with 30 holes (with grounding termination)	1	set									
MAIN : 200AT/200AF,3P,20KAIC, at 240V MCCB	1										
Branches :											
20AT,10KAIC,2P,MCCB	28										
Panel P-1 : 250A PANEL with 18 holes (with grounding termination)	1	set									
MAIN : 200AT/200AF,3P,18KAIC at 240V MCCB	1										
Branches :											
20AT,10KAIC,2P,MCCB	4										
30AT,10KAIC,2P,MCCB	12										
Panel P-2 : 250A PANEL with 18 holes (with grounding termination)	1	set									
MAIN : 200AT/200AF,3P,18KAIC at 240V MCCB	1										
Branches :											
20AT,10KAIC,2P,MCCB	4										
30AT,10KAIC,2P,MCCB	12										
Current transformer	3	set									
Three phase 200A Rectangular meter base	1	set									
Three phase (transformer rated) KilowattHour-Meter	1	set									
500 AMPERE AUTOMATIC TRANSFER SWITCH	1	set									
Sub-Total (11.0):										-	

DESCRIPTION	QTY	UNIT	UNIT COST			TOTAL UNIT COST	TOTAL	OVERHEAD/C	TAX	PROFIT	TOTAL
			MATERIALS	LABOR	TOOLS/EQUIP	DIRECT	AMOUNT (DC)	MISCEL			BID AMOUNT
12.0 Water and Sewer Lines	1	lot									
											Sub-Total (12.0):
											-
13.0 CR Tiles and Fixtures	1	lot									
											Sub-Total (13.0):
											-
14.0 Septic Tank											
Cement, Portland	60	bags									
Sand, washed	3	cu.m									
Gravel, 3/4" Crushed	6	cu.m									
6" CHB	421	pcs									
10 mm dia x 6meter def. bars gr. 60	60	pcs									
Tie Wire # 16	20	kilos									
4" PVC Tee	3	pcs									
2" PVC Clean Out	2	pcs									
											Sub-Total (14.0):
											-
TOTAL BID COST:											-

Submitted By:

NAME OF BIDDER