



Washed Sand	2	cu.m.									-	-
3/4" Gravel	4	cu.m.									-	-
10mmØ x 6m RSB	133	pcs.									-	-
16mmØ x 6m RSB	124	pcs.									-	-
Ga. #16 Tie Wire	64	kg.									-	-
											<b>Sub-Total</b>	-
<b>d.4 Plinth Beam (PB)</b>	3.98	cu.m.										
Portland Cement	36	bags									-	-
Washed Sand	2	cu.m.									-	-
3/4" Gravel	4	cu.m.									-	-
10mmØ x 6m RSB	133	pcs.									-	-
12mmØ x 6m RSB	30	pcs.									-	-
16mmØ x 6m RSB	94	pcs.									-	-
Ga. #16 Tie Wire	64	kg.									-	-
											<b>Sub-Total</b>	-
<b>d.5 Interior Stage Retaining Wall Footing (WF1)</b>	0.51	cu.m.										
Portland Cement	5	bags									-	-
Washed Sand	1	cu.m.									-	-
3/4" Gravel	1	cu.m.									-	-
10mmØ x 6m RSB	13	pcs.									-	-
Ga. #16 Tie Wire	1	kg.									-	-
											<b>Sub-Total</b>	-
<b>d.6 Exterior Front Steps Retaining Wall Footing (WF1)</b>	0.92	cu.m.										
Portland Cement	8	bags									-	-
Washed Sand	1	cu.m.									-	-
3/4" Gravel	1	cu.m.									-	-
10mmØ x 6m RSB	9	pcs.									-	-
Ga. #16 Tie Wire	3	kg.									-	-
											<b>Sub-Total</b>	-
<b>d.7 Slab on Grade (Interior Floor Stage) (plain cement finish)</b>	2.71	cu.m.										
Portland Cement	21	bags									-	-
Washed Sand	2	cu.m.									-	-
3/4" Gravel	3	cu.m.									-	-
10mmØ x 6m RSB	19	pcs.									-	-
Ga. #16 Tie Wire	3	kg.									-	-
											<b>Sub-Total</b>	-
<b>d.8 Slab on Grade (Exterior Front Steps)</b>	0.59	cu.m.										
Portland Cement	5	bags									-	-
Washed Sand	1	cu.m.									-	-
3/4" Gravel	1	cu.m.									-	-
10mmØ x 6m RSB	5	pcs.									-	-
Ga. #16 Tie Wire	1	kg.									-	-
											<b>Sub-Total</b>	-
<b>d.9 Slab on Grade</b>	16.22	cu.m.										
Portland Cement	146	bags									-	-
Washed Sand	9	cu.m.									-	-
3/4" Gravel	17	cu.m.									-	-
10mmØ x 6m RSB	130	pcs.									-	-
Ga. #16 Tie Wire	22	kg.									-	-
											<b>Sub-Total</b>	-
<b>d.10 Lintel Beams (All Door &amp; Window Headers)</b>	0.66	cu.m.										
Portland Cement	6	bags									-	-
Washed Sand	1	cu.m.									-	-
3/4" Gravel	1	cu.m.									-	-
10mmØ x 6m RSB	27	pcs.									-	-
12mmØ x 6m RSB	30	pcs.									-	-
Ga. #16 Tie Wire	14	kg.									-	-
											<b>Sub-Total</b>	-
<b>d.11 Roof Beams (RB)</b>	4.77	cu.m.										
Portland Cement	43	bags									-	-
Washed Sand	3	cu.m.									-	-
3/4" Gravel	5	cu.m.									-	-
10mmØ x 6m RSB	165	pcs.									-	-
16mmØ x 6m RSB	111	pcs.									-	-
Ga. #16 Tie Wire	64	kg.									-	-
											<b>Sub-Total</b>	-
											<b>Sub-Total (D)</b>	-









	Cement Waterproofing compound	3	bags								-	-
	Cementitious Waterproofing	2	gal								-	-
	100 mm.x 3.00m dia., Schedule 1000, PVC Pipe	1	pcs.								-	-
	100 mm. dia., Schedule 1000, Coupling (PVC)	2	pcs.								-	-
	100 mm. dia., Schedule 1000, Sanitary tee (PVC)	3	pcs.								-	-
	100 mm. dia., Schedule 1000, Clean Out (PVC)	3	pcs.								-	-
	PVC Solvent, 400cc	1	can								-	-
											-	-
n.4	<b>Plumbing Fixture</b>	<b>1.00</b>	L.s.									
	Water closet w/ Bidet hose, complete w/ fittings and accessories	1	set								-	-
	Wall Hung Lavatory, complete w/ fittings and accessories	1	set								-	-
	Wall Hung Urinal, complete w/ fittings and accessories	1	set								-	-
	Faucet	1	sets								-	-
	Stainless Floor Drain	1	set								-	-
											-	-
											<b>Sub-Total (N)</b>	<b>#REF!</b>
O.	<b>Tile Works</b>	<b>174</b>	sq.m.									
	<b>o.1 Tileworks</b>											
	50cm x 50cm Carpet Tile	720	pcs.								-	-
	30cm x 30cm Glazed Wall Tile	35	pcs.								-	-
	30cm x 30cm Unglazed Floor Tile	100	pcs.								-	-
	Tile Adhesive	3	bag								-	-
	Multibond Adhesive for Vinyl Tiles	7	pack								-	-
											<b>Sub-Total (O)</b>	<b>0.02</b>
											<b>Grand Total</b>	